

# Environmental Surveys & Site Evaluation

## Purpose

South Fork Wind is gathering soil samples to collect data to inform onshore cable installation.

To acquire these samplings, soil borings will be taken along the planned cable route. Each boring will be an approximately 4-inch wide hole and approximately 5–20 feet deep.

The borings will be installed using direct-push drill rig and will be backfilled once completed. Our contractor will responsibly dispose of any drill spoils generated from the activities at an approved solid waste facility.

All locations will be restored to their original condition upon completion. Locations where a groundwater monitoring well will be installed will be completed with a protective flush-mounted cover.

After soil sampling is complete, several of the borings will be converted to groundwater monitoring wells for collection of groundwater samples.

## CONTACT US

### Email

[info@southforkwind.com](mailto:info@southforkwind.com)

### Website

[southforkwind.com](http://southforkwind.com)

### Twitter

[@SouthForkWind](https://twitter.com/SouthForkWind)

## Timeline & Location

### → LIRR CORRIDOR

26 borings are anticipated to be completed within the two-mile section of the Long Island Rail Road (LIRR) corridor between Wainscott Northwest Road and Cove Hollow Road.

**Timeline:** Survey activity will begin along the LIRR corridor as early as December 14<sup>th</sup>. This activity will likely be completed by the end of the year.

All work will be conducted Monday through Friday between 7:00 a.m. and 7:00 p.m. There will be no work done on holidays.