

# Location of Underground Utilities

## Purpose

South Fork Wind will be opening test pits to locate and confirm the depth of existing underground utilities to inform the detailed design of the onshore cable route.

To acquire this data, test pits will be performed along the planned cable route. Each test pit will be approximately 19-inches by 19-inches.

The work will be performed using a combination of hand tools, including shovels, jackhammers and vacuum excavation equipment.

Exposed utilities will be measured, photographed and GPS located. Once utility locations and depths have been confirmed, the test pits will be backfilled and compacted to grade. The road opening will be restored.

A work exclusion-zone may be set-up around the test pit using traffic safety equipment, signage and traffic flaggers. Travel lanes will be maintained to accommodate traffic, emergency vehicles and access to homes.

## CONTACT US

### Email

info@southforkwind.com

### Website

southforkwind.com

### Twitter

@SouthForkWind

## Timeline & Location

### → Town Roads

19 test pits are anticipated to be completed within the right-of-way along the following roads: Beach Lane, Wainscott Main Street, Sayers Path, Wainscott Stone Road, Wainscott Northwest Road, Daniels Hole Road and Stephen Hands Path.

**Timeline:** Beginning as early as February 8, 2021, lasting approximately three weeks.

All work will be conducted Monday through Friday between 7:00 a.m. and 7:00 p.m.